

RESOLUTION NO. 22-R-34

A RESOLUTION TO AWARD A CONTRACT FOR EMERGENCY CONSTRUCTION SERVICES FOR THE SANITARY SEWER MAIN LINE AND RIGHT-OF-WAY SANITARY SEWER SERVICE LATERAL REPAIR AT 4403 MAGNOLIA DRIVE

WHEREAS, the City of Rolling Meadows is a home-rule community, and the City Council may waive formal bidding procedures if it determines that such action is in the best interest of its residents; and

WHEREAS, the Public Works Director is recommending that the City use Newberg Construction Company, Inc., RFD 3930, Long Grove, Illinois 60047, to repair the right of way sanitary service lateral and connection at the City owned main line sanitary sewer and a renewed sanitary service connection for the residence at 4403 Magnolia Drive as defined in the proposal attached hereto as Exhibit 1.

NOW, THEREFORE, BE IT RESOLVED by the Mayor and the City Council of the City of Rolling Meadows, Illinois as follows:

SECTION ONE: The Rolling Meadows City Council finds the public's interest would be served by waiving a formal bidding requirement to perform the emergency repair of the right of way sanitary service lateral and connection at the City owned main line sanitary sewer along with a renewed sanitary service connection for the residence at 4403 Magnolia Drive.

SECTION TWO: The City Council of the City of Rolling Meadows, Illinois, accepts, and authorizes the Public Works Director's signature on a proposal submitted by Newberg Construction Company Inc. in the amount of \$18,446.36 dated March 6, 2022, and attached hereto as Exhibit 1.


Funding for this repair work it to be provided from Utilities Fund, Emergency Sanitary System Repairs, Account #20.70.5035.54640.

AYES: Bisesi, Sanoica, McHale, Budmats, O'Brien

NAYS: 0

ABSENT: Vinezeano, Reyez

Passed and approved this 22th day of March 2022.



Joe Gallo, Mayor

ATTEST:



Judith Brose, Deputy City Clerk

**NEWBERG CONSTRUCTION COMPANY
INC.**

RFD 3930

Long Grove, IL 60047

847.438.5666

dig@newbergconstruction.com

www.newbergconstruction.com



Estimate

ADDRESS

The City of Rolling Meadows
3900 Owl Dr
Rolling Meadows, IL 60008
United States

ESTIMATE # 20262339

DATE 03/06/2022

EXPIRATION DATE 03/20/2022

PO#	JOB NAME	TYPE
K. CASEY- AWAITING PO	4403 MAGNOLIA	SEWER REPAIR

ACTIVITY	DESCRIPTION	QTY	RATE	AMOUNT
	NEWBERG CONSTRUCTION WILL PROVIDE LABOR AND EQUIPMENT TO REPAIR QTY: 2 6" SANITARY SEWER SERVICES CONNECTIONS AT 12" MAIN. Village of Rolling Meadows to provide; 1.) Barricades & traffic control 2.) Assist with reinstating homeowner water service. 3.) Asphalt and concrete patching.			
MOBILIZATION	PER JOB (Depending on scope of work, equipment required, distance to job)	1	1,600.00	1,600.00
EXCAVATOR ZX85	HOURLY RATE	2	65.18	130.36
HYDRAULIC BREAKER	DAILY RATE	1	400.00	400.00
EXCAVATOR ZX160	HOURLY RATE	12	95.06	1,140.72
PLATE COMPACTOR/JUMPING JACK	DAILY RATE	1	350.00	350.00
TOOL TRUCK	HOURLY RATE Tool Truck Includes misc. hand tools to support Sewer/Water crew. Qty: (1) Locator, (1) 2" Trash pump, (1) 20' suction hose, (2) 50' Discharge hose,	12	95.00	1,140.00

ACTIVITY	DESCRIPTION	QTY	RATE	AMOUNT
	(1) 4' x 7' Trench shield, Slings/Bridles, (6) Barricades, (1) Cut-off saw 14", (1) Rotating laser, (1) Pipe laser.			
OPERATOR ST	HOURLY RATE	12	136.37	1,636.44
LABOR FOREMAN ST	HOURLY RATE	12	115.00	1,380.00
LABORER ST	HOURLY RATE	12	113.08	1,356.96
LABORER ST	HOURLY RATE	12	113.08	1,356.96
LABORER ST	HOURLY RATE	12	113.08	1,356.96
TRENCH SHORING	8' X12' X5'	1	430.50	430.50
				Subtotal: 12,278.90

MATERIALS:

12" X 6" WYE	EACH	2	508.56	1,017.12
12" NON-SHEER COUPLING	EACH	2	263.64	527.28
12" SDR 26 PVC	LF	14	44.71	625.94
6" NON-SHEER	6" X6" NON-SHEER COUPLING	2	108.00	216.00
6" SDR 26 PVC	LF	28	11.04	309.12
6" SDR 26 PVC BEND	6" BEND	6	102.00	612.00
TRENCH BACKFILL	# 6 WASH (ALLOWANCE) TRUCKING COVERED IN HOURLY.	1	385.00	385.00
TRENCH BACKFILL	GRADE 9 (ALLOWANCE) TRUCKING COVERED IN HOURLY.	1	395.00	395.00
				Subtotal: 4,087.46

SPOIL REMOVAL	HOURLY TO WAUCONDA DUMP	16	130.00	2,080.00
NOTE: Pricing is based on an estimate of the hours required to mobilize, setup, complete project, and demobilize. Any savings on hours will be credited to the contract holder. Any overage will be billed to the contract holder at the rates listed on this estimate.				

IMPORTANT: Newberg Construction may require a 50% minimum deposit due at start of project. Final payment due at time of completion. Any work outside the original scope may require additional charges, and shall require approval from a company representative. Asbestos or other environmental by others. Newberg Construction can provide references. Staking by others. Permits and fees by others. Backfill will be to rough grade, final restoration, paving, and concrete repair by others unless otherwise listed in this estimate. Material pricing valid at time of quote, any increases will be billed as a pass through cost. Hydro excavation/daylighting of sensitive utilities may be required depending on utility

TOTAL

\$18,446.36

locates. This will be billed at an hourly rate discussed with contract holder prior to project start

Labor for T/M projects billed as:
ST is M-F 7-4,OT is X1.5 hourly rate, X2 on Sun and Holidays.

Accepted By

Accepted Date